BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHDULE-B

Name of Work: Construction Of RCC Drain & Covering Slab Adjacent to North Side Govt School Compund Wall (L/S) in Ward No.15, T.Dasarahalli Sub Division.

Sl. No	Description of work	Unit	Qty	Sanctioned Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	545.40	81.00	Rupees Eighty One Only
2	Plain cement concrete 1:3:6 mix with crushed stone aggregates 40m nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14days complete as per specifications.	Cum	36.86	3654.72	Rupees Three Thousand Six Hundred Fifty Four and Seventy Two Paise Only
3	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregates @ 0.43cum super plastisiser @3ltrs confirming to IS9103-1999 Reaffirmed-2008,machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	118.76	4846.32	Rupees Four Thousand Eight Hundred Forty Six and Thirty Two Paise Only
4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	q	71.00	7187.86	Rupees Seven Thousand One Hundred Eighty Seven and Eighty Six Paise Only
5	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specifications.	Sqm	982.80	298.92	Rupees Two Hundred Ninety Eight and Ninety Two Paise Only
6	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. complete as per specifications.	Sqm	245.70	1600.00	Rupees One Thousand Six Hundred Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 15 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading. complete as per specifications.	Cum	545.40	78.24	Rupees Seventy Eight and Twenty Four Paise Only

Signature of the Contractor

Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Executive Engineer,
Dasarahalli Division,